Lode Well Drilling, Inc.

13526 South 86th Avenue
Orland Park, Illinois 60462
Phone (708) 422-1306
Fax (708) 460-1409

PROPOSAL

Proposal Submitted To
Village of Palos Park
Attn: Fidel Castillo
8999 West 123rd Street
Palos Park, Illinois 60464
Office: 708.923.7170 / Fax: 708.361.2735
Cell: 708.935.2296 / Email: fcastillo@palospark.org

Date February 5, 2015

We hereby propose to furnish the materials and perform the labor necessary for the completion of:	
Lode Well Drilling proposes to: Remove old well tank. Remove and/or rework much of the current piping to accommodate a new plumbing manifold. New manifold to include a Grundfos variable speed drive allows for a much smaller wall-hung well tank. Mainfold to include: pressure sensor, tank, sample valve, gauge, boiler, drain and ball valve. All electrical will be reworked to accommodate new well. All piping and valves to be completed with copper and/or brass.	
ALL LABOR AND MATERIAL	$3,282.00

If accepted, please sign and return one copy to Lode Well Drilling, Inc.
All material is guaranteed to be as specified, and the above work to be performed in accordance with the drawings and specifications submitted for above work and completed in a substantial workmanlike manner for the sum as stated above plus or minus amount of footage with entire payment to be made upon completion of work. Any alteration or deviation from above specifications involving extra costs, will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry, fire, tornado and other necessary insurance upon above work. Workmen's Compensation and Public Liability insurance on above work to be taken out by Lode Well Drilling, Inc.
Thank you for your consideration!

NOTE: This proposal may be withdrawn by us if not accepted within 90 days.

Respectfully submitted,

Lawrence J. Lode

Lawrence J. Lode
State of Illinois Licensed Water Well Contractor
License #102-002698, Lode Well Drilling, Inc.

ACCEPTANCE OF PROPOSAL

The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

ACCEPTED BY: _____

Dated 2/23/2015

Lode Well Drilling, Inc.

13526 South 86th Avenue
Orland Park, Illinois 60462
Phone (708) 422-1306
Fax (708) 460-1409

PROPOSAL

Proposal Submitted To
Village of Palos Park
Attn: Fidel Castillo
8999 West 123rd Street
Palos Park, Illinois 60464
Office: 708.923.7170 / Fax: 708.361.2735
Cell: 708.935.2296 / Email: fcastillo@palospark.org

Date February 5, 2015

We hereby propose to furnish the materials and perform the labor necessary for the completion of:	
After evaluation, Lode Well Drilling has diagnosed well system problems as follows: Current well tank has a leaking bladder reducing the draw-down per pump cycle from 13.5 gallons to approximately 6.5 gallons. The resulting effect puts twice as much taxation on an already old pump. Information provided to Lode Well Drilling indicates that the current pump is as old as the building and (especially give tank issues) has a short life expectancy. Bottom Line: time to address this well system.	
Pull existing equipment from well. Replace old pump cable with new 10/3 Double Jacketed Pump Cable. Replace old couplings with new stainless steel couplings. Replace in-line check valve(s) with new brass check valve(s). Pull old underground cable and replace with new cable to include ground wire from well head to maintenance building.	
ALL LABOR AND MATERIAL	$3,891.00

If accepted, please sign and return one copy to Lode Well Drilling, Inc.
All material is guaranteed to be as specified, and the above work to be performed in accordance with the drawings and specifications submitted for above work and completed in a substantial workmanlike manner for the sum as stated above plus or minus amount of footage with entire payment to be made upon completion of work. Any alteration or deviation from above specifications involving extra costs, will be executed only upon written orders, and will become an extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control. Owner to carry, fire, tornado and other necessary insurance upon above work. Workmen's Compensation and Public Liability insurance on above work to be taken out by Lode Well Drilling, Inc.
Thank you for your consideration!

NOTE: This proposal may be withdrawn by us if not accepted within 90 days.

Respectfully submitted,

Lawrence J. Lode

Lawrence J. Lode
State of Illinois Licensed Water Well Contractor
License #102-002698, Lode Well Drilling, Inc.

ACCEPTANCE OF PROPOSAL

The above prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above.

ACCEPTED BY: _____

Dated 2/23/2015